

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-17

History of original corner establishment:

This corner was originally established by Eugene P. McCornack, U.S. Deputy Surveyor, under his Contract No. 398, dated July 2, 1881, during his surveys beginning on August 15, 1881. The original notes state that at the corner a 4' long by 4" square marked post was set 24" in the ground for the corner to Sections 2,3,34, and 35, from which:

- A 12" pine bears N25°E-23 lks, marked T8S R36E S34 BT.
- A 8" tamarack bears S10°E-17 lks, marked T9S R36E S2 BT.
- A 12" fir bears S45°W-20 lks, marked T9S R36E S3 BT.
- A 14" pine bears N40°W-16 lks, marked T8S R36E S34 BT.

In 1937, Otis Gould, U.S. Cadastral Surveyor, under special instructions dated Nov. 27, 1935, during his surveys in July through October, 1937, recovered this corner and changed it to refer to refer to Sections 2 and 3 only. Gould's notes state that at the corner point a marked brass cap on a 2" by 3' long iron post

Description of corner evidence found:

was set 27" in the ground with the marked orig. post buried at the base of the new monument, from which:

- A pine stump at ground level bears N25°E-23 lks (Old BT.).
- A tamarack, 14" in dia. bears S35°E-39 lks, with healed blaze. (Old BT.).
- A 36" tamarack bears N61°W-46 lks, marked T8S R36E S34 BT. Old BT-Obliterate marks
- A 8" fir bears S33°W-32 lks, marked T9S R36E S3 BT. (New BT).

Found a 2½" brass cap on a 2" iron pipe protruding 6" from an earth mound from which:

- A 18" lodgepole pine stump bears S32°E-25.7' with scribing vis. on open blaze.
- A 8" lodgepole pine bears S41°W-21.1' with scribing vis. on open blaze. (Gould's notes call this tree a fir).

The corner is located in an old skid trail and had been disturbed-reestablished corner position by measuring record distance from the SE and SW bearing trees.

Description of monument and accessories | established to perpetuate the original location of this corner:

Built a mound of stone around the monument to the top. From the monument:

- A 13" white fir bears S28°E-39.5' scribed T9S R36E S2 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post East of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

The cap is a standard GLO brass cap marked:

T8S R36E

S35

S3 | S2

T9S R36E

1937

This corner was maintained on September 24, 1985.

Witness: Bob English.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of Baker Co. Surveyor County of Baker
State of Oregon , I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

FILED 2-12-1986

BAXER COUNTY SURVEYOR

SURVEY NO. 9-36-85