

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-19

History of original corner establishment:

This corner was originally established by Eugene P. McCornack, U.S. Deputy Surveyor, under his Contract No. 398, dated July 2, 1881, during his surveys beginning on August 15, 1881. The original notes state that at the corner a 3' long by 3" square marked post was set 24" in the ground from which:

A 24" fir bears N45°W-40 lks, marked 1/4 S BT.
A 20" fir bears S88°E-48 lks, marked 1/4 S BT.

DIAGRAM

1/4 S2

T9S R36E

In 1937, Otis Gould, U.S. Cadastral Surveyor, under special instructions dated Nov.27, 1935, during his surveys in July through October, 1937, recovered this corner and changed it to refer to Section 2 only. Gould's notes state that at the corner point he set a marked brass cap on a 1" by 3' long iron post 27" in the ground from which:

A fir stump, 24" in dia. bears N21°W-40 lks, marked 1/4 S BT. (Old BT-Obliterate marks).

Description of corner evidence found:

A 30" fir bears S82°E-48 lks, with healed blaze. (Old BT).
A 60" fir bears S59°W-30 lks, marked 1/4 S2 BT. (New BT).

Found a 2 1/2" brass cap on a 1" iron pipe protruding 6" from a mound of earth and stone from which:

A 30" doug. fir bears S82°E-31.7' with healed blaze.
A 50" down and uprooted doug. fir bears S59°W-19.8'± with scribing visible on an open blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

Built a mound of stone to the top of cap on the monument. From the monument:

A 30" doug. fir bears S65°W-39.4' scribed 1/4 S2 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post East of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

The cap is a standard GLO brass cap marked:

1/4 S2

This corner was maintained on September 24, 1985.

1937

Witness: Bob English.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

County Surveyor _____ Baker
Office of _____ County of _____
State of Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____.

(COUNTY OFFICIAL)

(DEPUTY)

FILED 2-12-1986

BAKER COUNTY SURVEYOR

BY NO. 9-36-86