

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-21

History of original corner establishment:

This corner was originally established by Eugene P. McCornack, U.S. Deputy Surveyor, under his Contract No. 398, dated July 2, 1881, during his surveys beginning on August 15, 1881. The original notes state that at the corner a 4' long by 4" square marked post was set 24" in the ground for the corner to Sections 1, 2, 35, and 36 from which:

- A 24" fir bears N10°E-23 lks, marked T8S R36E S36 BT.
- A 24" fir bears S30°E-20 lks, marked T9S R36E S1 BT.
- A 8" tamarack bears S20°W-20 lks, marked T9S R36E S2 BT.
- A 20" fir bears N60°W-14 lks, marked T8S R36E S35 BT.

In 1937, Otis Gould, U.S. Cadastral Surveyor, under special instructions dated Nov. 27, 1935, during his surveys in July through October, 1937, recovered this corner and changed it to refer to Sections 1 and 2 only, and obliterated marks on bearing trees North of the township line. Gould's notes state that at the

Description of corner evidence found:

corner he set a marked brass cap on a 2" by 3' long iron post 27" in the ground from which:

- A 36" fir bears N10°E-23 lks, marked T8S R36E S36 BT. (Old BT- Obliterated marks).
- A 24" fir bears S30°E-20 lks, with healed blaze. (Old BT).
- A 18" tamarack bears S20°W-20 lks, marked T9S R36E S2 BT. (Old BT)
- A 36" fir bears N60°W-14 lks, marked T8S R36E S35 BT. (Old BT-Obliterated marks).

Found a 2½" brass cap on a 2" iron pipe protruding 6" from a earth mound from which:

- A 31" doug. fir bears S24°E-14.0' with healed blaze. (Old BT).
- A 18" western larch bears S21°W-13.7' with healed blaze. (Old BT).

Description of monument and accessories | established to perpetuate the original location of this corner:

Cleaned up area around the monument. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set a steel fence post East of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

The cap is a standard GLO brass cap marked:

This corner was maintained on September 23, 1985.

Witness: Bob English.

T8S R36E

S36
S2 | S1

T9S R36E

1937

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

County Surveyor _____ Baker
Office of _____ County of _____
State of Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)