


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Corner No. 1, Boulder Lode, also Corner No.1, Rainbow Lode, M.S. No. 447

History of original corner establishment:

Corner originally ESTABLISHED by C.M.Foster, U.S. Deputy Mineral Surveyor under instructions dated Sep. 25, 1901, for mineral survey no. 447.



Surveyor General records state: Beginning at Cor No 1, A pine post 4½ ft long 6 ins square, set 18 ins in ground surrounded with a mound of earth scribed Rainbow cor-1-447. Identical with the SW cor post of amended location also identical with cor no 1 of the Boulder Lode this survey. A tamarack 10 ins dia brg N40°20'E, 38.7 ft dist blazed Rainbow-1-447 BT. A pine 6 ins dia brs N88°20'E, 26.8 ft dist blazed Boulder cor-1-447 BT.

Corner RECOVERED and PERPETUATED by J.R.Mitchell, experienced corner recovery technician, as noted below. No record filed with Baker County Surveyor.


Description of corner evidence found:

Found a 2½" brass cap on 1" galvanized iron pipe in mound of earth and stone marked as shown beside from which:

OBT: A western larch 13" dia with partially healed blaze brs N40°20'E, 38.7' per record.

Other BT not found in old roadway.

JRM BTs: A lodgepole pine 9" dia brs N65°W, 18.3' dist mkd BL 1 MS 447 BT.




Description of monument and accessories | established to perpetuate the original location of this corner:

At position of JRM brass cap monument which is the best available evidence of original corner position...


Removed brass cap monument & replaced with 2 " x 30" aluminum pipe with 2½" aluminum cap 20" in ground surrounded with a mound of earth and stone. Set 6' steel fence post alongside with signs 54-2 & 54-9. Cap marked as shown in corner diagram. Painted 6" band of red around each OBT and JRM-BT.

Compass declination 20° East.

I hereby certify that the above corner monument was properly REMONUMENTED to U.S.F.S. standards by me and witnessed by Bill Gohring on October 14, 1987.



William L Hanley



Office of.....County Surveyor..... County of.....Baker.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED 2-2-88
 BAKER COUNTY SURVEYOR
 SURVEY NO. 9-36-101