

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 813

History of original corner establishment:

- A. William W. Elmer, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 813 surveyed the Elizabeth Dahl claim known as Pioneer, Pacific, and LaCross Lodes from 28 June, to 8 July, 1922 and approved by the U.S. Surveyor General's Office.

DIAGRAM

T 9S R36E WM

CDR 2
LaCross

SURVEYOR GENERAL'S RECORD STATES:

A pine post 4.5 ins. square at the top, 4 ft. long, set 2 ft. in the ground, with a mound of earth and stone, scribed 2-813-L.C., whence
A white fir 12 ins. dia. bears N2-41W., 46 ft., and
A black pine 8 ins. dia. bears N48-13E., 35.6 ft.
each blazed and scribed 2-813-LACROSS BT

Description of corner evidence found:

B. MONUMENT FOUND:

I found a 4"x4"x12" decayed remnant of pointed post 20" in the ground.

ACCESSORIES FOUND:

found sawn stump and down bole of bearing tree bears N5E, 44.7 ft. with scribing of "2 MS 813 LA" after opening blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/28/90

- C. At the position of the pointed post remnant, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 20" in the ground with a mound of stone to the top. The cap is marked:

2
LaCross
MS 813
1990

STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED

- 10" dia. Spruce bears S12E, 10.8 ft.; scribed 2 MS 813 LACROSS BT
10" dia. Western Larch bears N56E, 20.9 ft., scribed 2 MS 813 LACROSS BT
Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edwin A. Stryker
OREGON
JULY 15, 1988
EDWIN A. STRYKER
2060