

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 813

History of original corner establishment:

- A. William W. Elmer, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 813 surveyed the Elizabeth Dahl claim known as Pioneer, Pacific, and LaCross Lodes from 28 June, to 8 July, 1922 and approved by the U.S. Surveyor General's Office.

DIAGRAM
T 9S R36E WM

COR 3
LaCross

SURVEYOR GENERAL'S RECORD STATES:

A pine post 4 ins. square at the top, 4 ft. long, set 1.5 ft. in the ground with a mound of earth and stone, scribed 3-813-PIONEER, whence A forked yellow pine 3 ft. dia. bears N59-41E., 6.9 ft., and A yellow pine 30 ins. dia. bears N45-30E., 15.88 ft. each blazed and scribed 3-813-PION BT. Identical with Cor. No. 3, Pioneer and Cor. No. 2 Pacific lodes of this survey, previously described and which with the bearing trees I scribed 3-813-LACROSS

Description of corner evidence found:

B. MONUMENT FOUND:

I found a 3"x3"x2" remains of wood post 10" in the ground in stones.

ACCESSORIES FOUND:

36" dia. Ponderosa Pine stump rotted and decayed bears N72E, 8.7 ft.
30" dia. Ponderosa Pine stump rotted and decayed bears N53E, 16.6 ft. with axe marks and visible scribe of "P".

Description of monument and accessories I established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/13/90

- C. At the position of the pointed post remnant, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 10" in the ground on bedrock at point of post remains. Mounded earth and stone to 2" of top. Cap is marked

MS 813
PACIFIC 2 PIONEER 3
LACROSS 3
1990
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED

24" dia. Grand Fir bears N66W, 35.0 ft.; scribed 2 MS 813 PAC BT
16" dia. Douglas fir bears N30E, 44.0 ft.; scribed 3 MS813 PION BT
Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edwin A. Stryker
OREGON
JULY 15, 1983
EDWIN A. STRYKER
2060

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 11-16-1990
HARVEY COUNTY SURVEYOR
BOOK 83 9-36-125