

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 813

History of original corner establishment:

DIAGRAM
T 9S R36E WM

WITNESS COR 5
LaCross

- A. William W. Elmer, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 813 surveyed the Elizabeth Dahl claim known as Pioneer, Pacific, and LaCross Lodes from 28 June, to 8 July, 1922 and approved by the U.S. Surveyor General's Office.

SURVEYOR GENERAL'S RECORD STATES:

A pine post 4 ins. square at the top, 4 ft. long, set 1.5 ft. in the ground, with a mound of earth and stone, scribed WC 5 813 LACROSS, whence
A yellow pine 5 ft. in dia. bears S77E., 3 ft., and
A yellow pine 3.5 ft. in dia. bears S10E., 21.1 ft.
each blazed and scribed WC 5 813 LACROSS BT

Description of corner evidence found:

B. MONUMENT FOUND:

I found a 4"x3"x7" pointed rotted remains of wood post 12" in the ground

ACCESSORIES FOUND:

Dead and down Ponderosa Pine with blaze and visible scribe of "S 8". Root hole centerline bears N72E, 3.0 ft.
Ponderosa Pine sawn stump bears S8E, 20.6 ft. with no visible marks.

Description of monument and accessories I established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/14/90

- C. At the position of the pointed post remnant, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 20" in the ground with a mound of stone to the top. The cap is marked:

MS-813
WC-5
LACROSS
1990
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED

13" dia. Ponderosa Pine bears S52W, 45.0 ft.; scribed WC 5 MS 813 LACROSS BT
20" dia. Ponderosa Pine bears N31W, 42.3 ft., scribed WC 5 MS 813 LACROSS BT
Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with Declination set at 20 degrees east.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edwin A. Stryker
OREGON
JULY 15, 1983
EDWIN A. STRYKER
2060