


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 813

History of original corner establishment:

A. William W. Elmer, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 813 surveyed the Elizabeth Dahl claim known as Pioneer, Pacific, and LaCross Lodes from 28 June, to 8 July, 1922 and approved by the U.S. Surveyor General's Office.



SURVEYOR GENERAL'S RECORD STATES:

A pine post 4.5 ins. square, 4 ft. long, set 1.5 ft. in the ground with a mound of earth and stone, scribed 4-813-PACIFIC, whence
A red fir 14 ins. dia. bears S10E., 5.42 ft., and
A black pine 10 ins. dia. bears N57E., 48.4 ft., each blazed and scribed 4 813 PACIFIC BT.

B. Description of corner evidence found:
MONUMENT FOUND:

I found a 4"x4"x4" remains of wood post 10" in the ground with mound of stone on surface.


ACCESSORIES FOUND:

26" dia. Grand Fir with healed blaze and logging scar near blaze bears S8E, 6.2 ft.
No evidence of other BT

Description of monument and accessories I established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/13/90

C. At the position of the pointed post remnant, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 10" in the ground with a mound of stone to 2" of the top. The cap is marked:



NEW ACCESSORIES ESTABLISHED

22" dia. Grand Fir bears S56W, 37.3 ft.; scribed 4 MS 813 PACIFIC BT

Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Edwin A. Stryker
OREGON
JULY 15, 1983
EDWIN A. STRYKER
2060

FILED 11-16-1990
BAKER COUNTY SURVEYOR
SURVEY NO. 9-36-130