

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. R-21

History of original corner establishment:

Corner was originally established by William R. Gradon under G. L. O. contract No. 409, during May 26, to June 6, 1882. Surveyors General's notes state: "Set basalt stone 18 X 9 X 4 ins. 12 ins. in the ground for cor. to secs. 23, 24, 25 & 26, marked with 2 notches S. and 1 on E. sides from which: A pine 36 ins. in diam. bears N30°E, 47 lks. dist. marked T9SR36ES24 BT. A pine 24 ins. in diam. bears S50°E, 48 lks. dist. marked T9SR36ES25 BT. A pine 8 ins. in diam. bears S45°W, 55 lks. dist. marked T9SR36ES26 BT. A pine 24 ins. in diam. bears N45°W, 75 lks. dist. marked T9SR36ES23 BT. May 26, 1882."

DIAGRAM

T9S	R36E
S23	S24
S26	S25

Description of corner evidence found:

Found no trace of record corner stone. Measured S45°E, 49.5 ft. from a 28" Pine with visible scribing, from which a 36" Pine snag on ground, bears N30°E, 31.0 ft., some scribing found on stump, a badly leaning 30" Pine bears S40°E, 31.5 ft. with full scribing, and a 28" Pine with completely grown over blazes bears S49°W, 35.8 ft.

Field book #4, Page 19.

Corner is about 200' West of road on a steep West slope.

Description of monument and accessories established to perpetuate the original location of this corner

At the above described point set 2 1/2" X 30" galvanized pipe and brass cap marked:
Set pipe 20" in the ground to bedrock and placed mound of stone around to cap.
From which by magnetic declination of N20°E:
A 24" Pine bears N14°E, 90.6 ft. scribed T9SR36ES24 BT. A 20" Pine bears S57°W, 60.6 ft. scribed T9SR36ES26 BT. Placed 54-3s and brass washer stamped PLS 1051 on the new BTs. Old BTs have 54-3s. Painted blazes red and 6" red band around. Placed 54-4 on a steel fence post 5' North of the corner.

T9S	R36E
S23	S24
S26	S25

OR PLS 1051
1979

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Ronald Gilroy

November 21, 1979

Barry B. Barbour
**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of ...County...Surveyor..... County of Baker
State of Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 27 day of June 1980
James D. Henley by *Tam H. Hamley*
(COUNTY OFFICIAL) (DEPUTY)

June 27, 1980