

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original Survey by William R. Gradon under contract
No. 409 dated March 28 1882.

Set a basalt stone 18x10x8 ins 12 ins in the ground for cor
to secs 25, 26, 35 & 36 marked with 1 notch on S & E edges
from which.

A fir 14 ins diam bears N10° E 30 lks dist marked T9SR36ES25BT

A fir 12 ins diam bears S70° E 27 lks dist. marked T9SR36ES36BT

A fir 18 ins diam bears S55° W 8 lks dist marked T9SR36ES35BT

A Tamarack 14 ins diam bears N55°W 35 lks dist marked T9SR36ES26BT

DIAGRAM

T9S R36E

S26 | S25

S35 | S36

Description of corner evidence found:

At the corner location I did not find the original stone the ground is steep and
it may have rolled down the hill.

Live 24" Larch bears N55° W 23.1 ft with healed over blazes.

Burnt remains of a 14" Fir bears N10° E 19.8 ft with good scribes

There are also burnt remains of the other two BTs but there
was no visible scribes.

Description of monument and accessories I established to perpetuate the

original location of this corner:

At the intersect of the bearing trees I set a
3"x30" aluminum capped aluminum pipe 24"
in the ground in a mound of stone from which.

A 7" White Fir bears N63° 30' E 23.76 ft
marked T9SR36ES25BT nail in W base

A 4" White Fir bears S41° 30' E 13.64 ft
marked XBT nail in N base

An 8" White Fir bears S57° W 19.69 ft
marked T9SR36ES35 BT nail in W base

A 24" Tamarack bears N55°W 23.1 ft
marked original BT

MONUMENT STAMPED

T9S R 36E

S26 | S25

S35 | S36

1983

ORLS 1898

Bearings taken with a staff compass
declination 18½° East per 1980 Isogonic chart

Distances pulled to 60d nail with Brass
washer stamped LS 1898 driven in the side
center of the bearing trees.

I hereby certify that the above monument was
re-established as herein described
on August 9, 1983

7 sept. 1983

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Harry C. Hildebrand

OREGON
JULY 18, 1980
HARRY C. HILDEBRAND
1898

Office of.....Surveyor..... County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Sept. 7, 1983

BAKER COUNTY SURVEYOR

SURVEY NO. 9-36-24

☆ GPO—798-276

V-21