

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 477, during June and July 1902. The original notes state that at the corner a scribed tamarack post 4' long by 5" sq. was set 18" in the ground and surrounded with a mound of earth. From the post:
A 24" red fir bears S1⁰13' W-23.46'.
A 12" red fir bears N67⁰16' W-43.3'.
Both marked B.T.B.Mt.W.C.-477.

DIAGRAM

MS 477
ES BM
MS 421 WEC
Bald Mountain
WEC

Description of corner evidence found:

Found a mound of earth with rotted remains of the post in hole in center of mound from which:

A down, very rotten fir bears S1⁰13' W-23.5'± with fragmentary scribing and measuring nail. Could not attach signs due to the rotten condition.

Description of monument and accessories established to perpetuate the

original location of this corner:

Set a 2¹/₂" by 30" aluminum pipe with a 2¹/₂" aluminum cap 24" in the ground and surrounded with a mound of earth and stone from which:

An 8" white fir bears S75⁰E-7.9' scribed WEC-BM-477 BT.

An 11" white fir bears N25¹/₂⁰E-24.3' scribed WEC-BM-477 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-9 and 54-3 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post on claim line North of corner and attached sign 54-9.

Used steel tape and staff compass with 20⁰E declination, measured to the center of the bearing trees.

This corner was remonumented on July 24, 1985.

Witness: John Tuttle

Cap is marked:
MS 477

ES BM
MS 477 WEC

1985
PLS 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...27... day of.....Aug....., 1985
..... by
(COUNTY OFFICIAL) (DEPUTY)