

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 477, during June and July of 1902. The original notes state that at the corner a scribed tamarack post 4' long by 4" sq. was set 12" in the ground and surrounded with a mound of earth from which:

A 30" red fir bears N26°12'E-44.35'.
A 14" black pine bears S1°10'W-85.90'.
Both marked B.T.F. 2-477.

DIAGRAM

MS 477

F
Cor 2

Fairview Cor 2

Description of corner evidence found:

A 43" white fir bears N26°10'E-44.4' to face blaze and 45.3' to center line with scribing visible on open blaze (original bearing tree).
An 18" lodgepole pine stump bears S1°10'W-85.9' to face blaze and 86.5' to center line with scribing visible on butt of tree lying beside stump.

Re-established corner by record bearing and distance from the remaining bearing trees. Measured to face of blaze for corner re-establishment.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with a 2½" aluminum cap 20" in the ground and surrounded with a mound of stone from which:

An 8" douglas fir bears N1½°W-18.0' scribed 2-F-477 BT.
New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-9 and 54-3 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary NE of corner and attached sign 54-9 to one post and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was remonumented on July 24, 1985.

Witness: John Tuttle

Cap is marked:

MS 477

F
Cor 2

1985
PLS 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...27... day of.....Aug....., 1985
..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED

BAKER COUNTY SURVEYOR

SURVEY NO. 9-36-40

8-36-