

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was originally established by Arthur Philbrick under Mineral Survey No. 477, during June and July 1902. The original notes state that at the corner a scribed black pine post 4' long by 4" sq. was set 12" in the ground and surrounded with a mound of earth from which:
A 12" spruce bears S21°04'W-3.73'.
A 12" black pine bears N31°42'W-10.2'.
Both marked B.T.K.S.C.-477.

DIAGRAM

MS 477

K-SEC

Kitchi SEC

Description of corner evidence found:

Mound of earth and the remains of the rotted post at ground level from which:

A 10" lodgepole pine stump bears N31 3/4°W-10.5' with visible scribing (original bearing tree).

Note: There is a 15" spruce to the Southwest about 15' that has a catface facing the corner. There is also a root hole bearing S21°W-3 1/2' from the corner.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" by 30" aluminum pipe with a 2 1/2" aluminum cap 15" in the ground and surrounded with a mound of earth and stone from which:

A 12" white fir bears N24°W-8.6' scribed SEC-K-477 BT.

A 12" white fir bears S87 1/2°E-4.8' scribed SEC-K-477 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 and 54-9 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post on claim line near corner and attached sign 54-9.

Cap is marked:

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

MS 477

This corner was remonumented on August 28, 1985.

Witness: John Tuttle

K-SEC
BM

1985
PLS 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Baker
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the...2... day of..... Oct....., 1985
..... by
(COUNTY OFFICIAL) (DEPUTY)