

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was originally established by William Elmer under Mineral Survey No. 599, during August and September 1905. The original notes state that at the corner a scribed pine post 4' long by 6" sq. was set 2' in the ground and surrounded with a mound of earth from which:

A 12" tamarack bears N23°12'W-45.70'.

A 16" tamarack bears S56°03'W-39.06'.

Both are marked 3-599-D.D. B.T.

DIAGRAM

MS 599

DD
Cor 3

Devil's Dream Cor. 3

Description of corner evidence found:

Found a mound of earth and stone with the remains of the rotted post at ground level from which:

An 18" western larch bears S58½°W-39.9' with partly healed blaze (original bearing tree).

A 17" western larch bears N21°W-46.7' with healed blaze (original bearing tree).

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with a 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Placed the remains of the original post on the mound.

Attached sign 54-3 and 54-9 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary NW and NE of corner and attached sign 54-9 to one post and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:
MS 599

DD
Cor 3
1985
PLS 1106

This corner was remonumented on August 30, 1985.

Witness: John Tuttle

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 10-29-85

☆ GPO—798-276

BAKER COUNTY SURVEYOR

SURVEY NO. 9-36-73