

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-21

History of original corner establishment:

This corner was originally established by William R. Graddon, U.S. Deputy Surveyor, under his Contract No. 409, dated March 28, 1882, during May and June, 1882. The original notes state that at the corner a 3' long by 3" square marked post was set 24" in the ground from which:

A 10" pine bears N85°E-25 lks, scribed 1/4 S BT.
A 20" fir bears N80°W-15 lks, scribed 1/4 S BT.

DIAGRAM

T9S R36E
1/4
S14 | S13

Description of corner evidence found:

A 10" down lodgepole pine bears N85°E-16.5' to root hole with scribing visible on a partly healed blaze.
A down, rotten white fir bears N80°W-9.9' to root hole with scribing visible on a partly healed blaze.

The corner position was reestablished by record bearing and distance measurements from the found bearing trees.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap 24" in the ground and surrounded with a mound of earth and a few stones from which:

A 17" white fir bears N53 1/2°E-25.0' scribed 1/4 S13 BT.
A 10" white fir bears N43 1/2°W-13.4' scribed 1/4 S14 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post South of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was remonumented on September 24, 1985.

Witness: Willard Hulick.

Cap is marked:

T9S R36E
1/4
S14 | S13
1985
PLS 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 12-31-85

☆ GPO-798-276

BAKER COUNTY SURVEYOR

SURVEY NO. 9-36-81