

History of original corner establishment:

- A. Ira L. Hoffman, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 800 surveyed the Richard Woods claim known as Morning Star Lode from October 11, 1917 to September 19, 1918 and approved by the U.S. Surveyor General's Office 19 November, 1918. Otis O. Gould, U.S. Deputy Surveyor did a dependent resurvey under special instructions dated 27 Nov. 1935, and approved 17 August, 1937.

DIAGRAM

T 9S R36E WM

COR 4

SURVEYOR GENERAL'S RECORD STATES: (Otis O. Gould)

Set an iron post, 3 ft. long, 1 in. diam., 27 in. in the ground with the marked stake deposited at the base, for Cor. No. 4, Morning Star lode, with the brass cap marked

A fir, 12 ins. diam., bears N17-45E, 10 lks. dist. marks grown over. (Old B.T.)

Description of corner evidence found:

A fir, 14 ins. diam., bears N36E, 11 lks. dist. marks grown over. (Old B.T.)

4

from which

MS

800

1937

B. MONUMENT FOUND:

I found a 2.5" dia. brass cap on a 1.0" dia. iron pipe 18" exposed in stone mound under dead and down and rotted fir.
The cap was marked:

U S GENERAL LAND OFFICE SURVEY
PENALTY \$250 FOR REMOVAL

4

MS 800

1937

ACCESSORIES FOUND:

Dead 13" dia. Grand Fir bears N30E at 7.2 ft. with partly healed blaze and visible scribing.

Sound 23" dia. Grand Fir bears N46E at 7.6 ft. with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/11/90

- C. I removed the rotted fir and plumbed the monument to vertical in original hole in rock mound. Restacked rock mound to 5" exposure.

NEW ACCESSORIES ESTABLISHED

A Grand Fir, 8" dia. bears N68E, 10.9 ft.; scribed COR 4 MS 800 BT
A Grand Fir, 20" dia. bears S32W, 26.7 ft., scribed COR 4 MS 800 BT

Painted the blaze red on each BT

Painted a 6" wide red band around each BT

Placed brass washer marked "PLS 2060" at base of each BT blaze

Placed metal sign with bearing and distance information on each BT (54-3)

Placed metal ATTENTION sign on each BT (54-4)

Placed 6 ft. steel fence post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4) attached

I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edwin A. Stryker

OREGON
JULY 15, 1988

EDWIN A. STRYKER

2060

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 11-16-1990
CLERK COUNTY CLERK
SURVEY NO. 2-36-118