

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 375

History of original corner establishment:

- A. John Hagel, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 375, surveyed the Fred Knuthetal claim known as Myrtle Quartz Claim September 24,25, 1899 and approved by the U.S. Surveyor General's Office.

DIAGRAM

T 9S R36E WM

COR WCC
Myrtle

SURVEYOR GENERAL'S RECORD STATES:

Set a pine post 4 ins. square, 4.5 ft. long, 18 ins. in the ground with a mound of stones and earth around it marked it MYRTLE WCS 375 for west centre post. A bull pine 14 ins. in diam. blazed and marked MYRTLE WCS 375 BT bears S33-30E, 42.0 ft. The West centre location tree bears N69W, 44.5 ft.

Description of corner evidence found:

B. MONUMENT FOUND:

None

ACCESSORIES FOUND:

27" dia. Ponderosa Pine with healed blaze bears S33-30E, 42.0 ft.
Found a sawn stump bearing N64W, 46.6 ft. with no visible markings

CORNER WORK DONE ON 6/7/90

Description of monument and accessories | established to perpetuate the original location of this corner:

- C. At the locus of distance and reversed bearing from the original bearing tree, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 4" in the ground on bedrock with large mound of earth and stone to 4" of the top.
The cap is marked

WCC • MS 375
1990
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED

13" dia. Grand Fir bears N56W, 54.0 ft.; scribed WCC MS 375 BT

Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Edwin A. Stryker

OREGON
JULY 15, 1983

EDWIN A. STRYKER
2060

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

by (DEPUTY)

11-16-1990

9-36-119