

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 375

History of original corner establishment:

- A. John Hagel, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 375, surveyed the Fred Knuthetal claim known as Myrtle Quartz Claim September 24,25, 1899 and approved by the U.S. Surveyor General's Office.

DIAGRAM

T 9S R36E WM

COR 3
Myrtle Quartz

SURVEYOR GENERAL'S RECORD STATES:

Set a fir post 4 ins. square, 4.5 ft. long, 18 ins. in the ground, with a mound of earth around it, marked it MYRTLE COR 3 375 for Cor. No. 3.
A white pine tree 6 ins. in bears N56W, 20.0 ft.
A white fir tree 15 ins. in diam. bears S41E, 20.0 ft. both blazed and marked MYRTLE COR 3 375 BT. The SW cor. of location bears N84W, 212.0 ft

Description of corner evidence found:

B. MONUMENT FOUND:

Found mound of stone with remains of rotted post. Found 8"x4"x4" rotted remains of pointed post at 18" below surface.

ACCESSORIES FOUND:

29" dia. Douglas fir with healed blaze bears S40E, 20.4 ft.

CORNER WORK DONE ON 6/7/90

Description of monument and accessories I established to perpetuate the original location of this corner:

- C. At the position of the pointed post remnant, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 18" in the ground with mound of earth and stone to 4" of the top.
The cap is marked

COR 3 MS 375
1990
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED

18" dia. Douglas fir bears S70W, 23.3 ft., scribed COR 3 MS 375 BT

Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 15, 1983

EDWIN A. STRYKER
2060