

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

INDEX MS 375

**History of original corner establishment:**

**DIAGRAM**

T 9S R36E WM

COR 4  
Myrtle Quartz

- A. John Hagei, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 375, surveyed the Fred Knuthetal claim known as Myrtle Quartz Claim September 24, 25, 1899 and approved by the U.S. Surveyor General's Office.

**SURVEYOR GENERAL'S RECORD STATES:**

Set a fir post 4 ins. square, 4.5 ft. long, 18 ins. in the ground, with a mound of stones and earth around marked it MYRTLE COR 4 375 for Cor. No. 4. A red fir tree 11 ins. in diam. bears S87-30W, 49.2 ft., and a white fir tree 9 ins. in diam. bears S24-30E, 68.2 ft., both blazed and marked MYRTLE COR 4 375 BT

**Description of corner evidence found:**

**B. MONUMENT FOUND:**

Found 3"x4"x25" remains of wood post on hillside with scribing of "COR 4 MS 375" but could not locate any evidence of post below surface.

**ACCESSORIES FOUND:**

27" dia. Grand Fir with healed blaze bears S89W, 49.2 ft.  
(note: this bearing tree was tied into my traverse and the monument was set using solar traverse reverse bearing--the bearing shown is from my compass after monument was set.)

CORNER WORK DONE ON 6/7/90

**Description of monument and accessories I established to perpetuate the original location of this corner:**

- C. At the locus of distance and reversed bearing from the original bearing tree, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 18" in the ground on bedrock with large mound of earth and stone to 4" of the top.  
The cap is marked

COR 4 MS 375  
1990  
STRYKER PLS 2060

**NEW ACCESSORIES ESTABLISHED**

- 15" dia. Ponderosa Pine bears S6E, 27.0 ft., scribed COR 4 MS 375 BT  
16" dia. Grand Fir bears N60W, 25.1 ft., scribed COR 4 MS 375 BT

Painted the blaze red on each BT  
Painted a 6" wide red band around each BT  
Placed brass washer marked "PLS 2060" at base of each BT blaze  
Placed metal sign with bearing and distance information on each BT (54-3)  
Placed metal ATTENTION sign on each BT (54-4)  
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)  
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 15, 1983

EDWIN A. STRYKER  
2060