

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 375

History of original corner establishment:

- A. John Hagel, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 375, surveyed the Fred Knuthetal claim known as Myrtle Quartz Claim September 24,25, 1899 and approved by the U.S. Surveyor General's Office.

DIAGRAM

T 9S R36E W1

COR 5
Myrtle Quartz

SURVEYOR GENERAL'S RECORD STATES:

Identical with the NW cor. of location. A living yellow pine tree 18 in in diam., marked it MYRTLE COR NO 5 375. A yellow pine tree 20 ins. in diam. bears S67-15E, 8.5 ft. A tamarack tree 9 ins. in diam. bears N42-50E, 28.0 ft. Both blazed and marked MYRTLE COR 5 375 BT.

Description of corner evidence found:

B. MONUMENT FOUND:

Found the root collar and roots of the original corner tree.

ACCESSORIES FOUND:

16" dia. Western Larch snag with healed blaze bears N46E, 27.0 ft.
28" dia. Ponderosa Pine sawn stump bears S67E, 8.6 ft.

CORNER WORK DONE ON 6/7/90

Description of monument and accessories I established to perpetuate the original location of this corner:

- C. At the locus of root collar and root remains of the original corner tree set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 24" in the ground with large mound of stone and earth to the top.
The cap is marked

COR 5
MS 375
1990
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED

11" dia. Douglas fir bears N88W, 40.7 ft., scribed COR 5 MS 375 BT
39" dia. Ponderosa Pine bears S33W, 33.5 ft., scribed COR 5 MS 375 BT
Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-2)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

EDWIN A. STRYKER
JULY 15, 1982
2060