

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

- A. William W. Elmer, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 813 surveyed the Elizabeth Dahl claim known as Pioneer, Pacific, and LaCross Lodes from 28 June, to 8 July, 1922 and approved by the U.S. Surveyor General's Office.

INDEX MS 813

DIAGRAM

T 9S R36E WM

COR 4
LaCross

SURVEYOR GENERAL'S RECORD STATES:

A pine post 4.5 ins. square at the top, 4 ft. long, set 1.5 ft. in the ground, with a mound of earth and stone, scribed 4-813-LACROSS, whence
A red fir 10 ins. dia. bears S49-15W, 26.5 ft. blazed and scribed
4 813 LACROSS BT
No other bearings available.

Description of corner evidence found:

B. MONUMENT FOUND:

NONE

ACCESSORIES FOUND:

31" dia. Grand Fir with healed blaze (did not open) bears S49-15W, 26.5 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/14/90

- C. At the locus of reversed bearing and distance from the original BT, I set 2.5" dia. by 30" long aluminum pipe with 2.5" dia. aluminum cap. The pipe is set 20" in the ground with mound of earth and stone to top.
I mark the cap

MS 813
4
LACROSS
1990
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED

17" dia. Ponderosa Pine bears N51E, 41.2 ft.; scribed 4 MS 813 LACROSS BT

Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

EDWIN A. STRYKER
JULY 15, 1983
2060