

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-11

History of original corner establishment:

None - Corner established this survey

DIAGRAM

T9S R38E
C 1/4
S33
1991
PLS 848

Description of corner evidence found:

None - Corner established this survey

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, Set 26" in the ground.

From Which:

- A Ponderosa Pine, 10" in dia, bears S22°45'W, 20.2 ft, scribed: C1/4 S33 BT
- A Ponderosa Pine, 12" in dia, bears N78°30'W, 35.3 ft, scribed: C1/4 S33 BT
- A Ponderosa Pine, 14" in dia, bears S51°15'E, 70.2 ft, scribed: C1/4 S33 BT
- A Ponderosa Pine, 12" in dia, bears S09°15'E, 8.0 ft, scribed: C1/4 S33 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1906
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
March 29, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED _____ /-22-92
by _____ (COUNTY OFFICIAL) _____ (DEPUTY) _____ BAKER COUNTY SURVEYOR
SURVEY NO 9-37-208