


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Q-5

History of original corner establishment:

None.



Description of corner evidence found:

Not Set.

Description of monument and accessories established to perpetuate the original location of this corner:

T9S R37E
 S1/16
 S19 + S20
 OR PLS 1051
 1980

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 20" in the ground to bedrock and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 16" pine bears S30°W, 56.0 ft. scribed S1/16S19 BT. A 6" fir bears N16°E, 34.8 ft. scribed S1/16S20 BT. A 3/4" X 30" iron pipe bears 34 1/2°W, 2.71 ft. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-4 on steel fence post 5' North and 54-2 and 54-9 on steel fence post 5' West of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Robert R. Boling

May 15, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

**OREGON
OCT. 17, 1973
BARRY B. BARBOUR
1051**

Office of.....County Surveyor..... County of.....Baker.....
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 27 day of June, 1980.
James D. Hanley by *Tam Hanley*
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

June 27, 1980

FILED June 27, 1980

BAKER COUNTY SURVEYOR

SURVEY NO. 9-37-43

☆ GPO-799-276