


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. W-6-7

History of original corner establishment:

None.



Description of corner evidence found:

Not Set.

Corner is about 125' West of track road near dredge pond.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination fo N20°E:

A 10" pine bears S45°W, 52.3 ft. scribed 1/256S32 BT.

A 9" pine bears N43°W, 33.0 ft. scribed 1/256S32 BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs.

Placed 54-2 and 54-4 on steel fence post 5' West and 54-2 and 54-9 on steel fence post 5' South of the corner.

T9S R37E

NW-C-W-E

—+—
1/256S32

OR PLS 1051

1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Tracy Hall

April 18, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1951**

Office of... County Surveyor... County of... *Baker*
Oregon

State of... I hereby certify that the within instrument was filed in this office
for record on the... 27 day of... June... 19... 80

James D. Henley by *Tom Hamley*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

June 27, 1980

FILED *June 27, 1980*

BAKER COUNTY SURVEYOR

SURVEY NO. *9-37-50*