


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File NO, X-6

History of original corner establishment:

None



Description of corner evidence found:

Not Set

Corner falls on NE slope about 50' East of ridge.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

An 8" fir bears S07°E, 34.5 ft. scribed CW1/16S32 BT.

A 7" tamarac bears N29°W, 57.3 ft. scribed CE1/16S32 BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-2, 54-4 and 54-9 on steel fence post 5' West of the corner.

T9S R37E

W1/16

C —+— C

S32

OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Tracy Hall

April 18, 1980

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of... County Surveyor... County of... Baker
State of... Oregon... I hereby certify that the within instrument was filed in this office
for record on the... 27... day of... June... 19... 80
James D. Hanley... by... Tom Hanley...
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

June 27, 1980

FILED June 27, 1980

BAKER COUNTY SURVEYOR

SURVEY NO. 9-37-51