


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. X-6-7

History of original corner establishment:

None



Description of corner evidence found:

Not Set.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground. No rock in the area.

From which by magnetic declination of N20°E:

An 8" fir bears N66°W, 43.0 ft. scribed 1/256S32 on BT.

An 8" fir bears S22°W, 17.6 ft. scribed 1/256S32 on BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051.

Placed 54-2 and 54-4 on steel fence post 5' North and 54-2 and 54-9 on steel fence post 5' West of the corner.

T9S R37E
WW1/256
C — | — C
S32
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Tracy Hall

April 18, 1980

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of... County Surveyor... County of... Baker
State of... Oregon... I hereby certify that the within instrument was filed in this office
for record on the... 27... day of... June... , 1980
... James D. Hanley... by... Tom Hanley...
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-278

June 27, 1980

FILED June 27, 1980
BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-52