


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Y-6

History of original corner establishment:

None.



Description of corner evidence found:

Not Set.

Corner falls on south slope about 75' North of small drain.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 15" pine bears N74°E, 51.4 ft. scribed SW1/16S32 BT. A 9" pine bears N89°W, 23.6 ft. scribed SW1/16S32 BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' South and 54-2 on steel fence post 5' West of the corner.

T9S R37E
SW1/16 + S32
OR PLS 1051
1980

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Tracy Hall

April 17, 1980

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of... County Surveyor's County of ~~Wasco~~ Baker
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 27 day of June, 1980.
James D. Henley by *Tom Hamley*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

June 27, 1980

FILED June 27, 1980

BAKER COUNTY SURVEYOR

SURVEY NO. 9-37-56