


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-21

History of original corner establishment:

Corner established by William R. Graddon under GLO contract No. 416 dated August 19, 1881.



Surveyor General records state:

Set a quartz stone 16 x 8 x 5 ins, in the ground for cor to secs 25, 26, 35 & 36, marked with 1 notch on S and E edges; from which

- A pine 18 ins diam bears N 77° E, 119 lks dist mkd T 9 S R 37 E S 25 BT
- A pine 36 ins diam bears S 80° E, 117 lks dist mkd T 9 S R 37 E S 36 BT
- A pine 36 ins diam bears S 50° W, 50 lks dist mkd T 9 S R 37 E S 35 BT
- A pine 36 ins diam bears N 80° W, 85 lks dist mkd T 9 S R 37 E S 26 BT

Description of corner evidence found:


Original Section 35 bearing tree is a windblow snag with scribes "T 9 S R 37 E" visible with remaining roots and stump hole.

Stump and root holes are all that remain of the other original bearing trees.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established from the original Section 35 bearing tree set a 2 1/2 inch aluminum cap on a 2 inch aluminum pipe 31 inches long and projecting 6 inches out of the ground with a surrounding dirt and rock mound and a 6 foot steel fence post alongside with a sign 54-9 attached.

Aluminum cap marked thus:



New bearing trees established:

- A pine 9 ins diam bears S 75° W, 5.7 ft. dist. marked T 9 S R 37 E S 35 BT
- A pine 10 ins diam bears N 15° W, 36.5 ft. dist. marked T 9 S R 37 E S 26 BT
- A pine 10 ins diam bears N 55° E, 9.0 ft. dist. marked T 9 S R 37 E S 25 BT
- A pine 8 ins diam bears S 55° E, 37.3 ft. dist. marked T 9 S R 37 E S 36 BT

Each new bearing tree has a sign 54-3 attached below a 6 inch band of red paint and has a brass washer marked PLS 1639 nailed flush with BT blaze. A sign 54-9 is attached on the opposite side of tree from BT blaze. The original bearing tree snag windblow has signs 54-3 and 54-9 attached and a red band of paint around.

I hereby certify that the above described monument was properly established by me on August 8, 1984, and witnessed by Jim DeMastus and Daryl Schuchardt.

Surveyor Baker

Office of..... County of.....

State of Oregon..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL) (DEPUTY)

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639