


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Wm. W. Elmer, U.S. Deputy Mineral Surveyor, under instructions received from the United States Surveyor General for Oregon dated Oct. 23, 1906, and designated as Survey No. 679.



Surveyor General records state:

A pine post 3½ ft long 5 ins square set 1½ ft in the ground with a mound of earth and stone, scribed 4-679-FC 3-679-AGF.

A fir 24 ins dia bears N35°32'E 3.13 ft, a fir 18 ins dia bears N19°42'E 39.30 ft, both blazed and scribed 4-679-FC 3-679-AGF BT.

Description of corner evidence found:

Found lower 12 ins of original post with pointed end to depth of 18 ins.  
Found portion of original blaze with fragmentary scribes visible "679-B" and a rotten root hole.  
No trace of other bearing tree.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" aluminum cap on 2" aluminum pipe 30 ins long 25 ins in ground with 5 ins proj. out of ground with surrounding rock mound and 6 ft steel fence post alongside with sign 54-9 attached. Buried remains of original post alongside.

Aluminum cap marked as shown in corner diagram.

New bearing trees established:

A tamarack 15 ins dia bears N66½°W 4.4 ft marked 3-AGF-4-FC-679 BT.

A tamarack 14 ins dia bears S22½°W 22.0 ft marked 3-AGF-4-FC-679 BT.

Each original bearing tree and each new bearing tree has signs 54-3 and 54-9 attached below a 6 in band of red paint, additionally each new bearing tree has a brass washer marked PLS 1639 nailed flush with BT blaze.

I hereby certify that the above described corner monument was properly established by me and witnessed by Jim DeMastus and Daryl Schuchardt on May 13, 1985.

Witnessed: Jim DeMastus

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William L. Hanley*

**OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639**

Office of..... County Surveyor..... County of..... Baker  
Oregon  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

FILED March 14, 1986  
BAKER COUNTY SURVEYOR  
SURVEY NO. 9-37-96