


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Cor.No.3 Mountain Belle Lode MS 177.

**History of original corner establishment:** Corner ESTABLISHED by C.M.Foster, U.S. Deputy Mineral Surveyor, under instructions dated September 6, 1888, mineral survey No 177, for the Mountain Belle Quartz Mine. Surveyor General records state: Mound of rocks and post marked Mountain Bell Claim, Sta.No 3 Sur No 177. Corner RECOVERED by John Hagel U.S. Deputy Mineral Surveyor, under instructions dated October 19, 1899, mineral survey No. 378, for Wide West Lode. Surveyor General records state: (from corner No 4, Wide West Lode)...Cor No 1 Mountain Belle Lode bears S72°55'W, 27.0 ft.




Corner RECOVERED by Wm.W.Elmer, U.S. Deputy Mineral Surveyor, under instructions dated November 28, 1905, mineral survey No 653 A, for the Orleans Quartz Mining Claim. Surveyor General records state: (from corner No 1, Orleans Lode)... Cor No 3 Sur No 177, Mountain Belle Lode, a post 4 ins square set in the ground with a mound of earth and stone, scribed Mountain Belle, Sta No 3, Sur No 19, bears N29°27'W, 7.20 ft.

Corner RECOVERED & PERPETUATED by J.R.Mitchell, experienced corner recovery technician. No record filed with the Baker County Surveyor of his perpetuation of the corner as described below.

**Description of corner evidence found:**

Found a 2½" brass cap on 1" galvanized iron pipe with surrounding rock mound, brass cap marked as shown to right, from which...



Cor No 4 Wide West Lode, MS 378, brs N72°55'W, 27.0' dist per record and Cor No 1 Orleans Lode, MS 653 A brs S29°27'E, 7.2' dist per record, each perpetuated with a 2½" brass cap on 1" galvanized iron pipe.

NOTE: These corners were remonumented concurrently and a certified record of land corner monumentation has been prepared for each.

JRM BT: A white fir 11" dia with partially healed blaze brs S 7°W, 26.0' dist mkd MB 3 MS 177 BT.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At position of JRM brass cap monument...

Removed brass cap monument and replaced with a 2" x 30" aluminum pipe with 2½" aluminum cap 25" in ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram. Set 6' steel fence post alongside with sign 54-9 and 54-2 attached.

New bearing tree established:

A western larch 10" dia brs N04°E, 65.8' dist mkd MB-3-177 BT.

Attached signs 54-3 and 54-9 and painted face of blaze and 6" band of red paint around each BT.

Compass declination 20° East.

I hereby certify that the above corner monument was properly REMONUMENTED to U.S.F.S. standards by me and witnessed by Bill Gohring on November 20, 1987.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of.....County.....Surveyor..... County of...Baker.....  
State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)