

INDEX No. R-11

History of original corner establishment:

Corner was originally established in 1881 by Herman D. Gradon, under General Land Office Contract Number 416. Surveyor General's notes state: Set a sandstone 16x12x4 ins. 11 ins. in the ground for 1/4 sec. cor. marked 1/4 on N face: from which

DIAGRAM
T9S R37E
S21
1/4 -•-
S28
1991
PLS 848

A pine 24 ins. diam. bears N25°W, 74 lks dist. marked 1/4 S BT

A pine 6 ins. diam. bears S55°E, 55 lks dist. marked 1/4 S BT

Description of corner evidence found:

Found 16"x12"x4" stone set in the center of a mound of stone, tipped to the south. There are no marks apparent on the stone, however it is a rough, soft stone and it appears the marks have worn off.

Found the remains of a 24" ponderosa pine stump (no scribing visible) which bears N23°W, 48.8 feet. (Record: N25°W, 48.8 feet). No sign of the SE BT which was a 6" ponderosa pine. There are several low cut stumps in the general vicinity of this bearing tree.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, Set 20" in the ground, buried the corner stone along the north side of the pipe.

From Which:

- A Douglas Fir, 16" dia., bears N45°15'W, 7.2 ft., scribed: 1/4 S21 BT
- A Douglas Fir, 14" dia., bears N59°15'E, 30.4 ft., scribed: 1/4 S21 BT
- A Douglas Fir, 12" dia., bears S38°30'E, 13.0 ft., scribed: 1/4 S28 BT
- A Douglas Fir, 10" dia., bears S52°45'W, 8.8 ft., scribed: 1/4 S28 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
April 5, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED Jan 22 1992
by _____ (COUNTY OFFICIAL) _____ (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-182