

INDEX No. R-13

History of original corner establishment:

Corner was originally established in 1881 by Herman D. Gradon, under General Land Office Contract Number 416. Surveyor General Notes state:
 Set a post, 4 ft. long, 4 inches square 24 ins. in the ground for Cor. to Sec's 21, 22, 27 & 28 marked:
 T9S S22 on NE
 R37E S27 on SE
 S28 on SW and
 S21 on NW face, with 2 notches S and 3 notches on E edges: from which:

DIAGRAM

T9S R37E
S21|S22
 S28|S27
 1991
 PLS 848

- A pine 20 ins. diam. bears N65°E, 68 lks dist. marked T9S R37E S22 BT
- A pine 12 ins. diam. bears S60°E, 60 lks dist. marked T9S R37E S27 BT
- A pine 12 ins. diam. bears S10°W, 91 lks dist. marked T9S R37E S28 BT
- A pine 40 ins. diam. bears N25°W, 54 lks dist. marked T9S R37E S21 BT

Description of corner evidence found:

Found no remains of the original post.

Found the remains of the four original bearing trees:
 At center of search area found remains of a 40" stump and using record bearing and distance (S25°E, 35.64 ft.) from this stump established search area for other BT's and found:

A rotten 12" Ponderosa Pine stump with bottom portion of blaze face with part of the "BT" scribe visible. (Rec: S10°W, 60.06 ft.).

Remains of 20" P.Pine stump, no scribing visible (Rec: N65°E, 41.5 ft.).

Remains of 12" P. Pine stump, no scribing visible (Rec: N60°E, 39.60 ft.)


Description of monument and accessories I established to perpetuate the original location of this corner:

Using all four recovered original bearing trees established best fit for corner position and set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, Set 23" in the ground.

From Which:

- A W. Larch, 18" in dia., bears N23°30'W, 44.2 ft., scribed: T9S R37E S21 BT
- A P. Pine, 10" in dia., bears N43°15'E, 41.6 ft., scribed: T9S R37E S22 BT
- A D. Fir, 12" in dia., bears S42°30'E, 20.0 ft., scribed: T9S R37E S27 BT
- A P. Pine, 12" in dia., bears S68°30'W, 52.7 ft., scribed: T9S R37E S28 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.



This work is performed by:
 Douglas M. Ferguson PLS 848
 Witnessed by:
 D.Mitchell Ferguson & Rick Saul
 April 3, 1991
 Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
 State of _____ I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____ FILED 1-22-92
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
 SURVEY NO. 9-37-181