

INDEX No. R-15

History of original corner establishment:

Corner was originally established in 1881 by Herman D. Gradon, under General Land Office Contract Number 416. Surveyor General's Notes States:

DIAGRAM

T9S R37E
S22
1/4 -*-
S27
1971
(BLM CAP)

Set a quartz stone 24x8x4 ins. 18 ins. in the ground for 1/4 sec. cor. marked 1/4 on N face; from which:

A pine 40 ins. diam., bears N20°E, 12 lks. dist. marked 1/4 S BT

A pine 34 ins. diam., bears S75°E, 75 lks. dist. marked 1/4 S BT.

In 1971 Owen C. Chatters II, Cadastral Surveyor for the BLM remonumented this corner under Special Instructions dated May 3, 1957, Group 350. BLM record states: The 1/4 sec. cor. of secs. 22 and 27, monumented with the original quartz stone, 24x8x4 ins., firmly set 18 ins. in the ground, and in a mound of stone, with illegible chisel marks on N. face, from which the remains of the original bearing trees: A pine, 40 ins. diam., bears N20°E, 14 lks. dist., with healed blaze. (Record, 12 lks.). A pine, 26 ins. diam., bears S75°E., 65 lks. dist., with scribe marks 1/4 S BT visible on open blaze. At the corner point set an iron post, 28 ins. long, 2 1/2 ins. diam., 18 ins. in the ground, and in a mound of stone, 5 ft. base, to top, with brass cap mkd (SEE DIAGRAM) from which new bearing trees: a larch, 8 ins. diam., bears N21°E, 201 lks. dist., mkd. 1/4 S22 BT. A ponderosa pine, 10 ins. diam., bears S41°E, 30 lks. dist., mkd. 1/4 S27 BT. Deposit corner stone alongside iron post.

Description of corner evidence found:

Found 2 1/2" iron post with a 3 1/2" brass cap stamped as shown in diagram. Monument is projecting 8 inches out of the ground. Monument is solid and in good condition.

Original Pine stump 40" dia, with scribing visible, bears N 19°01'E, 9.17 ft. (BLM Rec: N20°E, 9.24 ft.)

W. Larch 12" dia., healed blaze, bears N 19°47'E, 132.63 ft., set by BLM (Rec: N21°E, 132.66 ft.)

P. Pine 14" dia., healed blaze, bears S43°35'E, 19.64 ft. set by BLM (Rec: S41°E, 19.80)

Original P. Pine snag 30" dia, no scribing visible, bears S76°26'E, 43.33 ft. (S75°E, 42.90 ft.)

Measurements to existing BT's taken with an Electronic Tacheometer with bearings based on the survey control network.

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.

From Which:

- A P. Pine, 14" in dia., bears S50°00'W, 7.1 ft., scribed: 1/4 S27 BT
- A P. Pine, 8" in dia., bears N51°30'W, 17.0 ft., scribed: 1/4 S22 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1963
DOUGLAS M. FERGUSON
Office 848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
April 1, 1991
Refer to Baker Co. Survey No. 9-37-181

County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED /-22-92
by _____ (COUNTY OFFICIAL) _____ (DEPUTY) BAKER COUNTY SURVEYOR

SURVEY NO. 9-37-184