

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-11

History of original corner establishment:

Corner established this survey.

DIAGRAM

T9S R37E
C1/4
S28
1991
PLS 848

Description of corner evidence found:

Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, Set 23" in the ground.

From Which:

- A Ponderosa Pine, 9" in dia., bears N50°15'W, 13.4 ft, scribed: C1/4 S28 BT
- A Ponderosa Pine, 8" in dia., bears N68°30'E, 42.7 ft, scribed: C1/4 S28 BT
- A Ponderosa Pine, 14" in dia., bears S55°15'E, 95.2 ft, scribed: C1/4 S28 BT
- A White Fir, 8" in dia., bears S30°45'W, 70.2 ft, scribed: C1/4 S28 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1983
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
March 28, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED 1-22-92
_____ by _____
(COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-181