

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-12

History of original corner establishment:

Corner established this survey.

DIAGRAM

T9S R37E
E 1/16
C-----C
S 28
1991
PLS 848

Description of corner evidence found:

Corner established this survey.

Description of monument and accessories I established

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, Set 12" in the ground and raised a mound of earth and stone 1 1/2' x 3 1/2' around the monument.

From which:

- A P. Pine, 12" in dia, bears N36°30'W, 31.3 ft, scribed: C-E 1/16 S28 BT
- A P. Pine, 12" in dia, bears N35°15'E, 25.6 ft, scribed: C-E 1/16 S28 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence posts with Land Survey Monument (54-9) and Property Boundary (54-2) signs 8' south and 5' east of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1909
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
April 1, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed 1-22-91
in this office for record on the _____ day of _____, 19____

(COUNTY OFFICIAL) by _____ (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-181