

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-14

History of original corner establishment:

Corner established this survey.

DIAGRAM

T9S R37E
W 1/16
C-----C
S 27
1991
PLS 848
RM

Description of corner evidence found:

Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Corner position falls in the center of a Douglas Fir, 16" in dia, which was scribed on the north face as follows: C-W 1/16 S27. Brass washer stamped PLS 848 was nailed on lower portion of the blazed face. Put Land Survey Monument (54-9) signs on north and south sides of the corner tree and a Location tag indicating the tree is the corner.

From Which:

A P. Pine, 16" in dia., bears S68°30'E, 23.8 ft., scribed: C-W 1/16 S27 BT

A 2½"x30" aluminum monument, set 23" in the ground, bears S45°W, 5.0 ft., stamped as shown in diagram with the letters RM and an arrow showing the bearing and direction to the corner.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) sign above blaze and Land Survey Monument (54-9) sign on back of tree as required. Painted a 6" red band above Bearing Tree sign. Measurements to BT and RM taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence posts with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5'south and 5' west of the corner tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1909
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
April 3, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED 1-22-92

(COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-189