

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-15

History of original corner establishment:

Corner established this survey.

DIAGRAM

T9S R37E
C1/4
S 27
1991
PLS 848

Description of corner evidence found:

Corner established this survey.


Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, Set 23" in the ground.


From Which:

- A Douglas Fir, 16" in dia., bears N32°45'W, 30.0 ft., scribed: C1/4 S27 BT
- A Lodgepole Pine, 6" in dia., bears N49°30'E, 47.9 ft., scribed: X BT
- A Douglas Fir, 10" in dia., bears S65°30'E, 17.7 ft., scribed: C1/4 S27 BT
- A Lodgepole Pine, 6" in dia., bears N63°15'W, 23.2 ft., scribed: X BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' south of the monument.



This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D.Mitchell Ferguson & Rick Saul
April 3, 1991
Refer to Baker Co. Survey No. 9-37-181



Office of _____ County of _____
 State of _____ I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____ FILED 1-22-92
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
 SURVEY NO. 9-37-190