

INDEX No. T-17

History of original corner establishment:

Corner was originally established in 1881 by Herman D. Gradon, under General Land Office Contract Number 416. Surveyor General's Notes state: Set a post 3 1/4 ft. long 3 ins. square 24 ins. on W face: from which

DIAGRAM
T9S R37E
1/4
S27|S26
1971
(BLM CAP)

A pine 8 ins. diam. bears N35°E, 28 lks dist. marked 1/4 S BT
A pine 8 ins. diam. bears N50°W, 19 lks dist. marked 1/4 S BT

In 1971 Owen C. Chatters II, Cadastral Surveyor for the BLM remonumented this corner under Special Instructions dated May 3, 1957, Group 350. BLM records states: The 1/4 sec. cor. of secs. 26 and 27, determined at record distance from the remains of the original bearing trees: A pine snag, 10 ins. diam., bears N38°E, 28 lks. dist., with scribe marks 1/4 S BT visible on open blaze. (Record N35°E). A pine, 12 ins. diam., bears N48°W, 19 lks. dist., with scribe marks 1/4 S BT visible on open blaze. (Record, N50°W). At the corner point set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground with brass cap mkd. (SEE DIAGRAM) from which: A white fir, 10 ins. diam., bears S37°E, 65 1/2 lks. dist., mkd. 1/4 S26 BT. A white fir, 11 ins. diam., bears S55°W, 68 1/2 lks. dist., mkd. 1/4 S27 BT. Deposit glass bottle alongside iron post.

Description of corner evidence found:

Found 2 1/2" iron post with a 3 1/2" brass cap stamped as shown in diagram. Monument is projecting 4 inches out of the ground. Monument is solid and in good condition.

A Ponderosa Pine 12" dia., scribed 1/4 S BT on open blaze, bears, N51°32'W, 12.03 feet. Established by the original Surveyor (Rec: N50°W, 12.54 ft.)

A Ponderosa Pine 8" dia., dead and down, scribed 1/4 S BT on open blaze, bears N39°33'E, 19.51 ft. Established by the original Surveyor (Rec: N35°E, 18.48 ft.)

A White Fir 12" dia., healed blaze, bears S38°26'E, 46.7 ft. Established by the BLM (Rec: S37°E, 43.23 ft.)

A White Fir 14" dia., healed blaze, bears S52°12'W, 44.95 ft. Established by the BLM (Rec: S55°W, 45.21 ft.)

Measurements to existing BT's taken with an Electronic Tacheometer with bearings based on the survey control network.

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.
From Which:

A Douglas Fir, 18" in dia., bears N53°15'E, 50.9 ft., scribed: 1/4 S26 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) sign above blaze and Land Survey Monument (54-9) sign on back of tree as required. Painted a 6" red band above Bearing Tree sign. Measurements to BT taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1909
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
April 2, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED 1-22-92
_____ by _____
(COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-181