


INDEX No. U-11

History of original corner establishment:

Corner established this survey.

DIAGRAM



Description of corner evidence found:

Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, Set 24" in the ground.

From Which:

- A P. Pine, 10" in dia., bears N18°45'E, 18.4 ft., scribed: C-S 1/16 S28 BT
- A P. Pine, 10" in dia., bears S30°45'E, 8.7 ft., scribed: C-S 1/16 S28 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and 5' west of the monument.

This work is performed by:
 Douglas M. Ferguson PLS 848
 Witnessed by:
 D. Mitchell Ferguson & Rick Saul
 March 29, 1991
 Refer to Baker Co. Survey No. 9-37-181

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

[Signature]
 OREGON
 JULY 12, 1928
 DOUGLAS M. FERGUSON
 848

Office of _____ County of _____
 State of _____ I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____ FILED 1-22-92
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
 SURVEY NO. 9-37-181