

INDEX No. U-13

History of original corner establishment:

Corner established this survey.

DIAGRAM

T9S R37E
S 1/16
S28|S27
1991
PLS 848

Description of corner evidence found:

Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, Set 24" in the ground.

From Which:

A Douglas Fir, 14" in dia., bears N73°30'W, 33.8 ft, scribed: S 1/16 S28 BT
A Douglas Fir, 10" in dia., bears N80°30'E, 32.2 ft, scribed: S 1/16 S27 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' west and 5' east of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 14, 1983
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D.Mitchell Ferguson & Rick Saul
April 1, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED 1-22-92

(COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-195