

INDEX No. V-11

History of original corner establishment:

Corner was originally established in 1881 by Herman D. Gradon, under General Land Office Contract Number 416. Surveyor General's Notes state: Set a post, 3 1/2 ft. long 3 ins. square, 24 ins. in the ground for 1/4 sec. cor. marked 1/4 S on N face: from which

DIAGRAM
T9S R37E
S28
1/4 S33
1971
(BLM CAP)

A pine 14 ins. diam. bears N15°W, 48 lks. dist. marked 1/4 S BT.

A pine 7 ins. diam. bears South 14 lks. dist. marked 1/4 S BT.

In 1971 Owen C. Chatters II, Cadastral Surveyor for the BLM remonumented this corner under Special Instructions dated May 3, 1957, Group 350. BLM records states: The 1/4 sec. cor. of secs. 28 and 33, determined at record bearing and distance from the remains of the original bearing tree: A pine, 18 ins. diam., bears N15°W, 48 lks. dist., with scribe marks 1/4 S BT visible on open blaze. A pine, 14 ins. diam., bears South, 14 lks. dist., with scribe marks 1/4 S BT on open blaze. At the corner point set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground with brass cap mkd. (SEE DIAGRAM) from which new bearing trees: A ponderosa pine, 14 ins. diam., bears N26°W., 91 1/2 lks. dist., mkd. 1/4 S 28 BT. A fir, 8 ins. diam., bears S30°W, 118 lks dist., mkd. 1/4 S33 BT.

Description of corner evidence found:

Found 2 1/2" iron post with a 3 1/2" brass cap stamped as shown in diagram. Monument is projecting 4 inches out of the ground. Monument is solid and in good condition.

Ponderosa Pine, 18" dia., healed blaze, bears N26°31'W, 59.54 ft. established by the BLM (Rec: N26°W, 60.39 ft.)

Douglas Fir, 14" dia., healed blaze, bears S27°25'W, 77.95 ft. established by the BLM (Rec: S30°W, 77.88 ft.)

Ponderosa Pine, 30" dia., scribing 1/4 S BT visible on open blaze, bears S2°41'W, 9.06 ft. Established by the original surveyor (Rec: South, 9.24 ft.)

Measurements to existing BT's taken with an Electronic Tacheometer with bearings based on the survey control network.

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.

From Which:

A White Fir, 16" in dia., bears N77°45'E, 22.3 ft., scribed: 1/4 S28 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 4" north and 4" south of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1963
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
March 29, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____

(COUNTY OFFICIAL)

(DEPUTY)

FILED 1-22-92

BAKER COUNTY SURVEYOR

SURVEY NO. 9-37-198