

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-13

History of original corner establishment:

Corner was originally established in 1881 by Herman D. Gradon, under General Land Office Contract Number 416. Surveyor General's Notes state:  
Set a post 3 1/2 ft. long 3 ins. square, 24 ins. in the ground for 1/4 sec. cor. marked 1/4 S on W face: from which

**DIAGRAM**

T9S R38E  
1/4  
S33|S34  
1971  
(BLM CAP)

A pine 24 ins. diam. bears S60°E, 38 lks. dist. marked 1/4 S BT.  
A pine 20 ins. diam. bears S40°W, 9 lks. dist. marked 1/4 S BT.

In 1971 Owen C. Chatters II, Cadastral Surveyor for the BLM remonumented this corner under Special Instructions dated May 3, 1957, Group 350. BLM records states: The 1/4 sec. for. of secs. 33 and 34, determined at record bearing and distance from the remains of the original bearing trees: A root hole, bears S60°E, 38 lks. dist., with a down pine alongside, 24 ins. diam., with the scribe marks 1/4 S BT visible on open blaze. A root hole, bears S40°W, 9 lks. dist., with a down pine alongside, 20 ins. diam., with scribe marks 1/4 S BT visible on open blaze. At the corner point, set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd. (SEE DIAGRAM) from which new bearing trees: A fir, 11 ins. diam., bears S40°E, 33 lks. dist., mkd. 1/4 S34 BT. A fir, 9 ins. diam., bears N78°W., 77 lks. dist., mkd. 1/4 S33 BT. Deposit granite stone, 11x8x2 ins., mkd. X, alongside iron post.

Description of corner evidence found:

Found 2 1/2" iron post with a 3 1/2" brass cap stamped as shown in diagram. Monument is projecting 4 inches out of the ground. Monument is solid and in good condition.

Douglas Fir, 18" dia., healed blaze, bears N81°55'W, 48.97 ft.  
Established by the BLM (Rec: N78°W., 50.82 ft.)

Douglas Fir, 18" dia., healed blaze, bears S43°08'E, 21.03 ft.  
Established by the BLM (Rec: S40°E, 21.78 ft.)

Measurements to existing BT's taken with an Electronic Tacheometer with bearings based on the survey control network.

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.

From Which:

A Ponderosa Pine, 10" in dia., bears N87°45'E, 29.4 ft, scribed: 1/4 S34 BT  
A Ponderosa Pine, 8" in dia., bears S52°30'W, 17.8 ft, scribed: 1/4 S33 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
JULY 12, 1929  
DOUGLAS M. FERGUSON  
848

This work is performed by:  
Douglas M. Ferguson PLS 848  
Witnessed by:  
D. Mitchell Ferguson & Rick Saul  
April 1, 1991  
Refer to Baker Co. Survey No. 9-37-181

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_ I hereby certify that the within instrument was filed  
in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ FILED \_\_\_\_\_ 1-22-97  
\_\_\_\_\_  
(COUNTY OFFICIAL) by \_\_\_\_\_ (DEPUTY) BAKER COUNTY SURVEYOR  
SURVEY NO. 9-37-20