

INDEX No. X-16

History of original corner establishment:

None - Corner established this survey.

DIAGRAM

T9S R37E
E 1/16
C-----C
S34
1991
PLS 848

Description of corner evidence found:

None - Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:


Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, Set 28" in the ground.

From Which:

A P. Pine, 14" in dia, bears S89°15'W, 12.5 ft., scribed: C-E 1/16 S34 BT
A P. Pine, 14" in dia, bears N46°15'E, 22.5 ft., scribed: C-E 1/16 S34 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and 4' west of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR


OREGON
JULY 12, 1983
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
April 5, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19 FILED 1-22-92
_____ by _____ BAKER COUNTY SURVEYOR
(COUNTY OFFICIAL) (DEPUTY) SURVEY NO. 9-37-211