

INDEX No. X-17

History of original corner establishment:

Corner was originally established in 1881 by Herman D. Gradon, under General Land Office Contract Number 416. Surveyor General's Notes state:
Set a post 3 1/2 ft. long, 3 ins. square, 24 ins. in the ground for 1/4 sec. cor. marked 1/4 S on W face: from which

DIAGRAM

T9S R37E
1/4
S34|S35
1971
(BLM CAP)

A pine 18 ins. diam. bears S70°E, 57 lks dist. marked 1/4 S BT.
A pine 24 ins. diam. bears West, 14 lks. dist. marked 1/4 S BT.

In 1971 Owen C. Chatters II, Cadastral Surveyor for the BLM remonumented this corner under Special Instructions dated May 3, 1957, Group 350. BLM records states: The 1/4 sec. cor. of secs. 34 and 35, determined at record distance from the remains of the original bearing trees: A pine, 18 ins. diam., bears S70°E, 57 lks. dist., with scribe marks 1/4 S BT visible on open blaze. A pine stump, size indeterminate, bears N85°W, 14 lks. dist., no marks visible. (Record, West). At the corner point, set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd. (SEE DIAGRAM) from which new bearing trees: A ponderosa pine, 8 ins. diam., bears N72°E, 99 1/2 lks. dist., mkd 1/4 S35 BT. A ponderosa pine, 7 ins. diam., bears S12°W, 37 lks. dist., mkd. 1/4 S34 BT. Deposit granite stone, 4x3x3 ins., mkd. X, alongside iron post.

Description of corner evidence found:

Found 2 1/2" iron post with a 3 1/2" brass cap stamped as shown in diagram. Monument is projecting 4 inches out of the ground. Monument is solid and in good condition.

Ponderosa Pine, 16" dia., healed blaze, bears N66°14'E, 65.54 ft. Established by the BLM (Rec: N72°E, 65.67 ft.)

Ponderosa Pine, 10" dia., scribing visible, bears S10°35'W 24.38 ft. Established by the BLM (Rec: S12°W, 24.42 ft.)

Ponderosa Pine, 24" stump, with "BT" scribe visible, bears S72°46'E, 37.09 ft. Established by the orig. surveyor (Rec: S70°E, 37.62 ft.)

Measurements to existing BT's taken with an Electronic Tacheometer with bearings based on the survey control network.

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.

From Which:

A Ponderosa Pine, 10" in dia, bears S62°15'W, 7.4 ft., scribed: 1/4 S34 BT
A Ponderosa Pine, 10" in dia, bears N18°30'E, 19.8 ft, scribed: 1/4 S35 BT

Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs. Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D. Mitchell Ferguson & Rick Saul
April 1, 1991
Refer to Baker Co. Survey No. 9-37-181

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19 _____ FILED _____ /-22-92
by _____
(COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-212