

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Description of corner evidence found: (continued.....)

Ponderosa Pine, 10" dia, healed blaze, bears S57°00'W, 136.50 ft. Established by PLS 1051

Measurements to existing BT's taken with an Electronic Tacheometer with bearings based on the survey control network.

Description of monument and accessories I established to perpetuate the original location of this corner:


Rebuilt mound of stone around PLS 1051's monument.

From Which:

5/8"x30" rebar with plastic cap marked PLS 848, bears N45°W, 8.0 ft.
5/8"x30" rebar with plastic cap with 1 groove, marked PLS 848, bears N45°E, 10.0 ft.

Placed rebar pins 26" in the ground and set steel fence with Land Survey Monument (54-9) and Bearing Tree (54-3) signs behind each rebar. Measurements to rebar taken with a magnetic compass, declination 20° East, and a nylon clad steel tape.

This work is performed by:
Douglas M. Ferguson PLS 848
Witnessed by:
D.Mitchell Ferguson & Rick Saul
April 1, 1991
Refer to Baker Co. Survey No. 9-37-181



Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____ FILED 1-22-92
_____ by _____
(COUNTY OFFICIAL) (DEPUTY) BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-213