

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner established by John Hagel, U.S. Deputy Mineral Surveyor, under instructions received from the United States Surveyor General for Oregon dated Oct. 19, 1899, and designated as Survey No. 378.

Surveyor General records state:

Beginning at Cor. No. 1, set a white fir post, 4 ins. square, 4 1/2 ft. long, 18 ins. in the ground with a mound of earth around it, marked Charl. C. 1-378.

A white fir tree, 20 ins. in diam., bears S40°30'W, 38.0 ft. blazed and marked Charl. C. 1-378 BT.

Corner was remonumented by: John R. Mitchell, an unlicensed Forester, as described by USFS Corner Card, dated 6/1/81.

Record states:

36" WF brs S40 1/2° W, 38' w/ scribing in opened blaze.

Set a 2 1/2" BC on 1" x 32" gal pipe, set 24" deep at cor. pt. in md of stone & earth, marked CH C1 MS 378 JRM 1981.

10" WF brs S61°W, 22'

6" WF brs S51°E 11 1/2', both marked CH 1 MS 378 BT.

Corner was perpetuated by: Leland Myers, per Baker County Survey 8-37-135/9-37-279 in 2003. No Corner Record for this Monument was found. It is apparent Myers accepted the Mitchell brass cap and stamped his number and date over the top of Mitchell's.

**Description of corner evidence found:**

\*Mis-stamped "T8S"

A 1 inch galv. iron pipe with a 2 1/2 inch brass cap, marked as shown. Firmly set 6 inches above ground, with a rock collar.

From which:

A 36 inch white fir (by Hagel) with visible scribe marks on cut open blaze, bears S40 1/2°W, 38.0 ft. to blaze face, 39.6 ft. to a 1 1/2 inch SS washer mkd: PLS 699 in left side center, alive & healthy.

A 9 inch white fir (by Mitchell) with healed blaze, bears S51°E, 11.5 ft to 1 1/2 inch SS washer mkd: PLS 699 in left side center, alive with dead top.

A 14 inch white fir (by Mitchell) with healed blaze, bears S61°W, 22.1 ft to 1 1/2 inch SS washer mkd: PLS 699 in left side center, alive & healthy.

Monument falls West 0.25 miles from Fruit Creek Road; approximately 3,000 feet northerly of the intersection with NF-5540 Road.

**Description of monument and accessories I established to perpetuate original location of this corner:**

Added Bearing Tree and Land Survey Monument signs as needed.

NAD 83 Geodetic Position

Lat. 44°49'02.2" N  
Long. 118°12'53.0" W

Established by: Garmin ETREX 32x

I hereby certify that the corner is monumented and accessories taken as described using a steel tape and a Warren Knight staff compass, set with a declination of 14° East.

Witnesses: David Quittschreiber, Justin Seal

September 21, 2023

T 9 S R 37 E  
MS 378  
1 CH

CHARLESTON  
Cor. 1

T8S R37E  
MS 378  
CH1/  
2003  
PLS 699

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Kristina Powell*

OREGON  
MAY 9, 2017  
KRISTINA POWELL  
91201

EXPIRES 12-31-24

FILED January 8, 2024  
BAKER COUNTY SURVEYOR  
SURVEY NO. 9-31-395

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner established by John Hagel, U.S. Deputy Mineral Surveyor, under instructions received from the United States Surveyor General for Oregon dated Oct. 19, 1899, and designated as Survey No. 378.

Surveyor General records state:

To Cor. No. 2, a post, previously described, identical with the SW location Cor. identical with Cor. No. 1 Century Lode.

A white fir tree, 9 ins. in diam., bears N77°20'E, 25.4 ft.  
A white fir tree, 6 ins. in diam., bears N54°30'E, 23.2 ft.  
Both blazed and marked Charl. C. 2-378 BT.

Corner was remonumented by: John R. Mitchell, an unlicensed Forester, as described by USFS Corner Card, dated 6/1/81.

Record states:

Rotted post in md of earth & stone.

20" WF brs S58°E, 17.6' w/HB.  
18" DF brs S77°E, 25.4' w/HB.  
18" WF brs S56°E 17' w/HB.

Set a 2 1/2" BC on 1" x 32" gal pipe, set 28" deep in original hole & md of stone, marked CH C2 MS 378 JRM 1981.

11" WF brs S47 1/2°W, 37' & marked CH2 MS378 BT.

Corner was remonumented by: William L. Hanley, as described by Baker County Corner Report No. 8-37-117, filed 2-18-88.

Record states:

Found a JRM 2 1/2" brass cap on 1" galvanized iron pipe with surrounding rock mound, brass cap marked as shown to the right, from which:

OBT: A white fir 26" dia. with fully healed blaze brs S58°E, 17.6' dist per record.  
A white fir 17" dia. with fully healed blaze brs S81°E, 17.0' dist (record, S86°E, 17.0' dist)  
A douglas fir 17" dia with fully healed blaze brs N79°E (record, N77°20'E), 25.4' dist per record.  
A sawed fir stump 18" dia brs N54°30'E, 23.2' dist per record.

JRM BT: A white fir 11" dia with partially healed blaze brs S49 1/2°W, 37.0' dist mkd CH 2 MS 378 BT.

At position of JRM brass cap monument...

Removed brass cap monument & replaces with a 2" x 30" aluminum pipe with 2 1/2" aluminum cap 25" in ground, surrounded with mound of earth & stone. Cap marked as shown in corner diagram. Set 6' steel fence post alongside with sign 54-9 & 54-2 attached.

No new bearing trees established.

Painted 6" band of red paint around each OBT & JRM BT, also painted blaze red, attached signs 54-3 & 54-9 to all BTs.

Compass declination 20° East.

I hereby certify that the above corner monument was properly remonumented to USFS standards by me and witnessed by Bill Gohring on November 9, 1987.

Continued on page 2 of 2

T 9 S R 37 E  
MS 378  
1C / 2 CH

CHARLESTON  
Cor. 2

CENTURY  
Cor. 1

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Kristina Powell*

OREGON  
MAY 9, 2017  
KRISTINA POWELL  
91201

EXPIRES 12-31-24

FILED January 8, 2024  
BAKER COUNTY SURVEYOR  
SURVEY NO. 9-31-396