

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Description of corner evidence found:

A 2 1/2 inch galvanized iron pipe with a 3 1/4 inch BLM brass cap, marked as shown. Firmly set 6 ins. above ground.

From which:

A 24 inch pine stump (by G.L.O.) no visible scribe marks, bears N40°E, 30 links.

A 36 inch pine stump (by G.L.O.) with visible scribe marks, bears S31°E, 80 links.

SW BT (by GLO), not found.

A 9 inch western larch (by BLM) with healed blaze, bears N10°E, 75.2 feet (Record, 105 lks.), alive but distressed by parasitic mistletoe.

A 15 inch Douglas fir (by BLM) with healed blaze, bears S59°E, 82 links, alive and healthy.

A 13 inch lodgepole pine (by BLM) with mostly healed blaze and visible scribing, bears S20°W, 36 links, alive and healthy.

A 12 inch fir snag (by BLM) with healed blaze, bears N72°W, 23 links.

A steel T-post bears North 5.0 feet; with two (2) signs: Attention, Property Boundary

A steel T-post bears South 5.0 feet; with sign: Property Boundary

Description of monument and accessories I established to perpetuate original location of this corner:

New Bearing Tree:

An 8 inch tamarack scribed "X BT" on single blaze, bears S62°W, 63.2 feet; measured to a 3/4 inch brass washer mkd: "LS 91201", at the right side of tree center.

A Land Survey Monument sign was added to the South steel T-post.

NAD 83 Geodetic Position

Lat. 44°45'35.0" N
Long. 118°11'43.6" W


Established by: Garmin ETREX 32x

I hereby certify that the corner is monumented and accessories taken as described using a steel tape and a Warren Knight staff compass, set with a declination of 14° East.


Witnesses: David Quittschreiber, Justin Seal

October 4, 2023

2 of 2



R-9



FILED January 8, 2024
BAKER COUNTY SURVEYOR
SURVEY NO. 9-37-402

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Kristina Powell
OREGON
MAY 9, 2017
KRISTINA POWELL
91201
EXPIRES 12-31-24