



The quarter corner between Secs. 5 and 8, T. 9 S., R. 39 E., W.M. has been destroyed by farming.

The location was reestablished by traverse between the found section corners for these sections and ties to Corner No. 1 and Corner No. 8 of the Levi W. Nelson Mining Claim, recovered during this survey. Corner No. 8 was also found.

The original field notes of the Levi W. Nelson Claim mineral survey describe the obliterated 1/4 corner as being 10.4 chains from the L. W. N. Claim Cor. No. 1 and on the North line of the claim. Corner No. 1 is the NW claim corner and Corner No. 8 is the NE claim corner.

I reestablished the 1/4 corner according to the mineral survey notes tie. This yields a bearing and distance from NW corner of Sec. 8 to 1/4 corner = S. 89° 23' 10" E., 2658.16 feet and from 1/4 corner to NE section corner = S. 88° 36' 15" E., 2652.7 feet.

Both section corners are marked by mining rails, the NE corner is known to have been reset with this rail March 31, 1911.

MAP OF SURVEY

THE RELOCATION OF OBLITERATED 1/4 CORNER BETWEEN SECS. 5 & 8, T. 9 S., R. 39 E., W.M. BAKER CO., ORE.

Survey traverse June, 1975
 Cor. set Aug. 17, 1977
 Scale 1"=200'
 For Mike Nelson and City of Baker

FILED Aug. 18, 1977
 BAKER COUNTY SURVEYOR
 SURVEY NO. 9-39-22

