



Corners No. 1, 8 & 11 of the Levi W. Nelson Placer Claim are found in place; they consist of wood posts in mound or stones. The Southwest and Southeast cors. of Sec. 5, T. 9 S., R. 39 E., W.M. are found, marked by pieces of small-gage (mining) rails. The South 1/4 Sec. 5 is marked by a 1/2-inch steel rod (rebar), established by county surveyor. The original field notes of the Levi W. Nelson Claim describe the North line of claim lying along the South line Section 5. No tie was given to Southeast cor. Sec. 5.

The above survey shows these two lines (section & claim) are not in fact coincident as previously described. A part of the mining claim lies in Sec. 5.

The Levi W. Nelson Claim mineral survey in 1891.
 Section 5 subdivision survey = 1864
 Section 8 " " " = 1879
 County surveyor reset cors. to Secs. 4, 5, 8 & 9 in 1911.

MAP OF SURVEY

THE NORTH LINE OF LEVI W. NELSON PLACER MINING CLAIM & THE LINE BET. SECS. 5 and 8, T. 9 S., R. 39 E., W.M., AND THE CITY-OWNED ROAD THROUGH THE SUBJECT PROPERTY.

July 1 - Aug. 22, 1977 Scale: 1" = 200'
 For Mike Nelson

FILED Aug. 29, 1977
 BAKER COUNTY SURVEYOR
 SURVEY NO. 9-39-24

