

surveyor's distance between the East section corners of Section 5, the quarter corner is returned as closely as possible to its original position. It is marked with a brass cap monument as a part of this survey.

The South quarter corner and its accessories have been destroyed by farming. Original filed notes of the Levi W. Nelson Mining Claim mineral survey describe the quarter corner being 10.4 chains from the L. W. N Claim Corner No. 1, and on the North line of the claim. The mineral survey ties were then used to reestablish the quarter corner in its original position, using the found L. W. N. Corners No. 1 and 8. It is now marked with a 5/8-inch steel rebar.

The North and West quarter corners were declared "lost", and proportionate measurements employed for determining the coordinates of these corners. Neither was monumented in the field during this survey.

A perimeter traverse around the subject property made ties to all existing visible items of culture and monumentation. The intent of the sellers and buyers of the various parcels became evident when comparison was completed of the metes and bounds descriptions with the lines of occupation and monumentation. The result of that investigation is shown on the accompanying map of survey, on which the exterior boundaries of the city-owned property are described and indicate the found and recent monumentation established in the field. The survey was completed December, 1980.

with
9-39-30
12-4-80

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley

OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

FILED Dec. 4, 1980

BAKER COUNTY SURVEYOR

SURVEY NO. 9-39-30